PRESTAGE FARMS GRAIN ANNEX



Owner

Prestage Farms of South Carolina, LLC

Size/Capacity

410,000 bushel

Completion Time

6 months

Younglove's Services

- Conceptual design
- Structural engineering
- General construction
- Construction management
- Slipform concrete construction
- Equipment installation

Camden, South Carolina

This project consisted of two 50-foot-diameter by 140-foot-high continuous slipform silos with 9-inch-thick walls. The transfer of grain to the new silos is through the existing whole grain distributor to a 16,000-bushel-per-hour drag conveyor; and the reclaim from the silos feeds a 120-ton-per-hour drag conveyor back to the existing feed mill grinding system. A 120-ton-per-hour reclaim bucket elevator was installed to recirculate the grain from silo to silo. A flush-floor aeration system rated at 1/10 cfm per bushel was also provided in each silo.



