WENGER'S FEED MILL



Owner Wenger's Feed Mill, Inc.

Size/Capacity 50'-0" x 100'-0" x 162'-0"

Completion Time

10 months

Younglove's Services

- General construction
- Slipform concrete construction
- Equipment installation

Shippensburg, Pennsylvania

Our first project for Wenger's Feed Mill, Inc., included only the construction and equipment installation of a 162-foot-tall slipform structure containing 82 bins in a 50-foot by 100-foot area.

Adjacent to the main mill structure is a 36-foot by 20-foot by 96-foot-tall grinding slipform structure with four 10-foot-square bins.

An approximate total of 3,400 cubic yards of concrete and 270 tons of reinforcing steel were used in this project. Because of the amount and dimensions of the bins, it was necessary to place concrete from exterior and overhead concrete buggy paths.



